

**SURVEY & REMONUMENTATION**

**MAR 03 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**RECORDED**

1997 DEC 10 PM 3:54

For corners in **SECTION**

Dickinson  
(County)  
Breitung Twp.

Located In:

Corner Code #

1. Public Land Survey	T <u>40N</u> R <u>30W</u>	M.C. <u>36</u>
	T ___ R ___	W. of L-11
	T ___ R ___	#003
	T ___ R ___	M.C. <u>35/36</u>
2. Property Controlling in Section	S ___ T ___ R ___	N. of K-12
	S ___ T ___ R ___	Other # <u>#004</u>
3. Miscellaneous Property in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	

REGISTER OF DEEDS  
DICKINSON COUNTY  
RON NEWMAN, CLERK

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert F. Perkins, in a field survey on Oct. 29, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M.C. 25  
MEANDER CORNER 36  
Post by James H. Mullett, D.S. 1849  
Original Bearing Trees  
Cedar 4" N50°E 13 Lks.  
Tamarack 10" S70°E 25 Lks.

M.C. 35/36  
MEANDER CORNER 35/36  
Post by James H. Mullett, D.S. 1849  
Original Bearing Trees  
Birch 6" S7°E 32 Lks.  
Tamarack 8" S28°W 33 Lks.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE CORNER UNDER MICHIGAN PUBLIC ACT 74 OF 1970 AT A MEETING HELD ON 12-9-97

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M.C. 25  
M.C. 36  
No Evidence of Original Corner or Accessories Found.  
It appears from the Remains of Trees in the Water that the Lake Level was raised at some time subsequent to the Original Survey, probably by the construction of the Outlet Control Structure. As a result the Original Meander Corners were Lost.  
Corner Location Researched in 1996 Remon. Program.

M.C. 35/36  
No Evidence of Original Corner or Accessories Found.  
It appears from the Remains of Trees in the Water that the Lake Level was raised at some time subsequent to the Original Survey, probably by the construction of the Outlet Control Structure. As a result the Original Meander Corners were Lost.  
Corner Location Researched in 1996 Remon. Program.


COUNTY REPRESENT.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M.C. 25  
M.C. 36  
Set 2 1/2" Stamped D.C. Remon. Corner 1232.00' West of 1/4 Corner 25/36 on alignment of ancient fence line running West from 1/4 Corner and has a Bearing of S89°35'45"W.  
New Witnesses:  
Spruce 10" N75°E(M.B.) 2.25' Nail/Tag  
Spruce 7" S36°E(M.B.) 19.38' Nail/Tag  
Cedar 6" S32°W(M.B.) 17.47' Nail/Tag  
Maple 4" N14°E(M.B.) 10.65' Nail/Tag

M.C. 35/36  
Set 2 1/2" Stamped D.C. Remon. Corner 1291.80' Due North of 1/4 Corner 35 and 36, 4' from High Water Mark.  
New Witnesses:  
Cedar 4" S37°E(M.B.) 10.68' Nail/Tag  
Cedar 3" N46°W(M.B.) 7.76' Nail/Tag  
Cedar 3" S03°E(M.B.) 37.22' Nail/Tag  
Cedar 3" S38°W(M.B.) 31.88' Nail/Tag  
Centerline dirt Road ± 16' South

Signed by Robert F. Perkins  
Surveyor's Michigan License No. 12027



Date Nov. 26, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER **002** PAGE **338**