

RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 29 AM 10:31

For corners in

Dickinson
Breen Twp. (County)

Located In:

Corner Code #

1. Public Land Survey

T 41NR 27W

G-7

T R

I-8

T R

T R

2. Property Controlling in Section

S T

T R

SURVEY & RESTORATION

3. Miscellaneous Property in Sec.

S T

T R

MAR 24 2000

REGISTER OF DEEDS
DICKINSON COUNTY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ SECTION _____

5. Private Claims _____

I, Robert F. Perkins, in a field survey on Jan. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7							●						
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-7 Section Corner 15-16-21 & 22
John Burt, D.S. 1850
Set Y. Birch Post
Original Bearing Trees
Tamarack 16" S53°E 46' Lks.
Hemlock 20" N30°W 1.08' Lks.

I-8 ¼ Corner 22/23
John Burt, D.S. 1850
Set Cedar ¼ Post
Original Bearing Trees
Hemlock 12" S76°W 26' Lks.
Sugar 18" N53°E 12' Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7 No Evidence of Original Corner or Accessories Found.
Found Iron Bar 2' East of Road C/L at East-West Fence Line.
3 Existing B.T.'s

I-8 No Evidence of Original Corner or Accessories Found.
Found Iron Bar buried in Road at Location that agrees with D.C.R.C. 1937 Survey.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-23-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 Accept iron bar as described in "B" above as Best Remaining Evidence of Corner Location.
Set 3½" Stamped D.C. Remon.
Witness Corner 33.0' West of Bar.
New Witnesses
Tamarack 12" N26°E(M.B.) 40.58'
Tamarack 10" S88°E(M.B.) 32.55'
Tamarack 12" S62°W(M.B.) 57.60'
Set Carsonite Marker at W.C.

I-8 Accepted Iron Bar described in "B" above as Best Remaining Evidence of Corner Location. Set 3½" Stamped D.C. Remon. Witness Corner 16.10' South of Iron Bar.
New Witnesses
Power Pole N50°E(M.B.) 41.40' Nail/Tag
Spruce 10" S60°W(M.B.) 35.02' Nail/Tag
Fd. Corner of Barn S43°W(M.B.) 115.11'

Signed by Robert F. Perkins

Date Nov. 5, 1999

Surveyor's Michigan License No. 12027