

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1999 NOV 29 AM 10:31

For corners in

Dickinson  
(County)  
Breen Twp.

Located In:

Corner Code #

1. Public Land Survey

T 41NR 27W

G-8

T R

H-7

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

MAR 24 2000

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

SECTION \_\_\_\_\_

I, Robert F. Perkins, in a field survey on Jan. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-8 West 1/4 Corner, Section 22  
Cedar 1/4 Post by John Burt July 1850  
Original Bearing Trees  
Tamarack 8" S43°W 9 Lks.  
Tamarack 12" N73°E 16 Lks.

H-7 North 1/4 Corner, Section 22  
Tamarack 1/4 Post by John Burt 1850  
Original Bearing Trees  
Spruce 5" N39°E 104 Lks.  
Tamarack 14" S16°W 96 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 No Evidence of Original Corner or Accessories Found.  
Found 1" Solid Iron Bar buried 8" ± 1' West of County Road C/L  
1 Newer Bearing Tree  
Corner shown in D.C.R.C. Field Notes Circa 1937 and accepted and used on prior Surveys.

H-7 No Evidence or Original Corner or Accessories Found.  
Established Corner Location on Line between N.E. and N.W. Corners of Section 22 and 1.25' West of Mid-Point to agree with prior Surveys in Section.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PLEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-23-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: ROD B...

G-8 Accepted iron bar described in "B" above as Best Available Evidence of Corner Location.  
New Witnesses  
Set 3 1/2" Stamped D.C. Remon. Witness  
Corner 33.00' West of Iron Bar.  
P.Pole #90-25935 N27°W(M.B.) 68.84' Nail/Tag  
Cedar 8" N65°E(M.B.) 52.71' Nail/Tag  
Cedar 12" (Existing B.T.) S57°E(M.B.) 47.40'  
Placed Carsonite Marker at W.C.

H-7 Set 2 1/2" Stamped D.C. Remon. Corner at above described Location.  
Spruce 6" N14°E(M.B.) 8.08' Nail/Tag  
Spruce 4" S40°E(M.B.) 15.65' Nail/Tag  
Spruce 3" S07°E(M.B.) 18.36' Nail/Tag  
Spruce 5" S42°W(M.B.) 17.80' Nail/Tag  
Placed Carsonite Marker 1.2' South

Signed by Robert F. Perkins

Date Nov. 5, 1999

Surveyor's Michigan License No. 12027