

**SURVEY &
REMONUMENTATION**

APR 27 1995

RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

2005 JUN -8 PM 2:47

COMMISSION

For corners in

Dickinson
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey Sec. 2 | T <u>41N</u> R <u>27W</u> | <u>J-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1890 AT A MEETING HELD ON 6-7-94
RFP
COUNTY REPRESENTATIVE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

North one-quarter corner of Section 2, T41N, R27W

I, John R. Garske, in a field survey on April, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1846- Township boundary by Austin Burt: West 40.00 ch. set cedar post. Cedar 10 - N77°W, 28 links; Spruce 12 - N7°E, 30 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories remain.

I established corner position in the intersection of county roads running north, south and east. This position is consistent with previous surveys and the location of the deeded county road running west, the R/W of which was acquired entirely north from section line 66 feet in width. A 1978 survey by Robert Perkins, RLS, was used to establish the corner position at the centerline road location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a Dickinson County monument consisting of a 3/4" x 36" aluminum rod and a 2 1/2" stamped aluminum cap set 6" below surface of gravel road and established the following references:

- Ref. mon (stamped Dick. Co. monument) - S45°W, 35.20 feet
- Tamarack 6" - S23°E, 87.79 feet
- Power Pole #74-3422 - N45°E, 67.68 feet
- Old wood guard rail post - N53°W, 79.04 feet

Signed by John R. Garske Date 5/2/94
Surveyor's Michigan License No. 28410



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1990

Liben 2 page 96