

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T41N R27W
T. 41. NR. 28W. . .

Dickinson COUNTY

DESCRIPTION OF CORNER Section corner common to sections 30 and 31, T41N R27W and sections 25 and 36, T41N R28W.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap.

WITNESSES TO CORNER Hard maple 5" N21E 45½ links, marked X NBT.

Hard maple 4" N19W 53½ links, marked X NBT.

Aspen 8" S4W 39 links, marked S 36 NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from NBT 8" aspen S4W 39 links in excellent condition. NBT made by Forestry Division survey crew 4-6-59 when they placed this corner. Corner was pushed out by bulldozer in spring of 1961. NBT 4" W. ash S70W 8 links was also pushed out by bulldozer.

Corner was replaced in proper position by H. S. Peterson and C. R. Ryberg on 5-24-62.

SURVEYORS SEAL



SIGNED Henry S. Peterson DATE 5-25-62
REGISTERED LAND SURVEYOR