

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 41 NR. 27W

Dickinson COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 22 and 27.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap.

WITNESSES TO CORNER Cedar 6" N 15 W 34 links, marked 1/4 S NBT

Yellow birch 14" S 52 W 27 links, marked 1/4 S NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one original cedar bearing tree in good condition with a few green branches still remaining on the tree. (cedar 10 S63W 15) Two old wood posts about 3 feet west of corner. No evidence of other cedar original bearing tree.

Corner was placed and witnessed on 24 May 1962 with Clarence R. Ryberg.

SURVEYORS SEAL

*Henry S. Peterson*

SIGNED Henry S. Peterson  
REGISTERED LAND SURVEYOR

DATE 5-25-62