

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. <u>3</u> , R. <u>28</u> E. <u>W.</u>	C-5
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____ S. _____, R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S. _____, R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 22, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner C5 (Section Corner 7, 8, 17, & 18, T41N, R28W):**  
 Cedar post (Not found. See B for subsequent monuments)  
 Cedar 16 S44W 27 (Possibly found. No subsequent accessories found.)  
 Cedar 12 N64E 10 (Not found. " " " " )

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner C5:** Restored by first reconstructing the original survey random line for the 3 miles between Sec. Cor. 17, 18, 19, & 20 and Sec. Cor. 5, 6, 31, & 32, (T41-42N, R28W) from the field note calls to natural features and then applying the same corrections to the true corners as were theoretically used in the original survey to establish the intervening section and quarter-section corners. This procedure was necessitated by the fact that the calls to natural features are valid only as to the random line, not having been adjusted to the actual distances on the corrected lines. The random line reconstruction revealed that the actual length of the three miles is considerably shorter than the original record says (comparable shortages were found on the range line 1 mile west (over)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner C5:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Sugar Maple 6 N43°E (mag.) 1.2 ft. "S 8, NBT"  
 Sugar Maple 5 S55°W (mag.) 16.0 ft. "S18, NBT"  
 Hemlock 6 N39°W (mag.) 30.9 ft. "S 7, NBT"  
 Declination 4°40' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE May 25, 1978

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

