

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 28 X. W.	E-5
2. PROPERTY CONTROLLING IN SECTION 16	T. 41 N. R. 28 X. W.	1
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on_____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E5 (Section Corner 8, 9, 16, & 17, T41N, R28W):

- Y. Birch post (Not found. No subsequent monuments found.)
- Sugar 12 S32W 28 (Not found. No subsequent accessories found.)
- Lynn 12 N50E 23 (Not found. No subsequent accessories found.)

Corner 1 (West 1/16 corner between Sections 9 & 16, T41N, R28W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E5: Restored 5/8/78 basically by reconstructing the original survey random line from which the corner was originally set, the identified points on which were Sec. Cor. 4, 5, 8, & 9 and a double stream crossing south of the subject corner bet. Sec. 15 & 16. (Natural features given in the original field notes are on the random line, not the true line). The latitude of the subject corner was determined proportionately, and the departure by offsetting from the original random line the computed original correction.

Corner 1: Established 7/12/78 on line between Sec. Cor. 20.027 ch. W and 1/4 cor. 20.027 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 8 S51°E (mag.) 23.6 ft. "S16, NBT"
 Sugar Maple 7 S36°W (mag.) 26.1 ft. "S17, NBT"
 Declination 4°10' West.

Corner 1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 9 S38°W (mag.) 17.1 ft. "1/16S, BT"
 Sugar Maple 6 S15°E (mag.) 13.7 ft. "1/16S, BT"
 Declination 10°05' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger
CHIEF OF SURVEY PART
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

