

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(DICKINSON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> ^{N.} X , R. <u>28</u> ^{K.} W.	F-5
2. PROPERTY CONTROLLING IN SECTION <u>16</u>	, T. <u>41</u> ^{N.} X , R. <u>28</u> ^{K.} W.	2
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} S. , R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner F5 (1/4 corner between Sections 9 & 16, T41N, R28W):
 Sugar Maple post (Not found. No subsequent monuments found.)
 Ironwood 8 S30W 24 (Not found. No subsequent accessories found.)
 Sugar 18 N18E 12 (Not found. No subsequent accessories found.)

Corner 2 (East 1/16 corner between Sections 9 & 16, T41N, R28W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner F5: Restored 5/8/78 on line between Sec. Corners 40.054 ch. to E and to W.
Corner 2: Established 7/12/78 on line between Sec. Cor. 20.027 ch. E and 1/4 cor. 20.027 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner F5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 7 S39°W (mag.) 6.3 ft. "1/4S, NBT"
 Sugar Maple 7 N37°W (mag.) 2.7 ft. "1/4S, NBT"
 Declination 9°30' West.
Corner 2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 6 N59°E (mag.) 16.0 ft. "1/16S, BT"
 Sugar Maple 6 S12°W (mag.) 5.7 ft. "1/16S, BT"
 Declination 11°55' West.

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 16, 1979
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 13581