

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	(DICKINSON COUNTY) LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> ^{N.} S. , R. <u>28</u> ^{X.} W.	<u>G-5 & G-6</u>
2. PROPERTY CONTROLLING IN SECTION <u>16</u>	T. <u>41</u> ^{N.} S. , R. <u>28</u> ^{X.} W.	<u>14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. , R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER _____

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner G5 (Section Corner 9, 10, 15 & 16, T41N, R28W):

- Cedar post (Probably found. Found 2 rotted posts and 7/8" iron rod.)
- Cedar 24 S45E 24 (Probably found. No subsequent accessories found.)
- Cedar 12 N 7W 17 (Possibly found. No subsequent accessories found.)

Corner G6 (1/4 corner between Sections 15 & 16, T41N, R28W):

- Ironwood post (Not found. No subsequent monuments found.)
- Sugar 10 S74W 26 (Not found. No subsequent accessories found.)
- Sugar 10 N52E 35 (Not found. No subsequent accessories found.)

Corner 14 (South 1/16 corner between Sections 15 & 16, T41N, R28W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G5: Restored 5/8/78 at site of vertical streak trace of an old post (probably original) found in ground where 2 old rotted posts lay on the ground alongside an iron rod. Found a badly rotted cedar stump, apparently of about 24" size, at proper bearing & distance from post, and scraps of cedar in vicinity of the 2nd BT. Corner lies 1/2 to 1 ch. N of swamp edge (indefinite edge).

Corner G6: Restored 6/15/78 on line between Sec. Cors. 40.064 ch. to N and to S. Position agrees with swamp edge N and hill top S.

Corner 14: Established 6/15/78 on line between Sec. Cor. 20.032 ch. S and 1/4 cor. 20.032 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap (replaces iron rod).

- Sugar Maple 9 N56°W (mag.) 17.0 ft. "S 9, NBT"
- Cedar 11 S12°E (mag.) 47.6 ft. "S15, NBT"

Declination 12°05' West

Corner G6: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap

- Sugar Maple 6 S43°E (mag.) 7.3 ft. "1/4S, NBT"
- Sugar Maple 5 N16°W (mag.) 27.1 ft. "1/4S, NBT"

Declination 8°20' West.

Corner 14: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap

- Sugar Maple 9 S43°W (mag.) 19.6 ft. "1/16S, BT"
- Sugar Maple 5 N86°E (mag.) 18.9 ft. "1/16S, BT"

Declination 7°15' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 10, 1979
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

