

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 41 N. 28 W.	C-7
2. PROPERTY CONTROLLING IN SECTION 20 _____	T. 41 N. 28 W.	2
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner C7 (Section Corner 17, 18, 19, & 20, T41N, R28W):**
 Hemlock post (Not found. No subsequent monuments found.)
 Cedar 10 N24E 9 (" " " " accessories ")
 Cedar 16 S35W 9 (" " " " " ")
- Corner 2 (East 1/16 corner between Sections 17 & 20, T41N, R28W):**
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C7: Restored on 8/22/77 basically by reconstructing the original survey E & W random line, from reference to an original corner 1/2 mile E and to 3 stream crossings about 1 mile E, and stream crossings in the mile to the W and the corner on the range line west. The theoretical original corrections from random line points to established corners were then applied in reverse order to determine the probable location of the original random line, from which, in turn, the locations of the missing corners, such as this one, were determined. Corner thus established bears N0°30.0'W 39.997 ch. from an original cor. to S and N89°38.5'W 40.355 ch. from an original cor. to E. It also conforms to the original field note call to "descend from post" when going S from it.

Corner 2: Established 11/10/77 on line between Sec. Cor. 19.909 ch. E and 1/4 cor. 19.909 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner C7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 6 N84°E (mag.) 31.7 ft. "S17, NBT"
 W. Spruce 8 N87°W (mag.) 24.3 ft. "S18, NBT"
 Declination 0°30' West
- Corner 2:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Balm of Gilead 3 N28°W (mag.) 9.1 ft. "1/16S, BT"
 W. Birch 12 S17°W (mag.) 35.0 ft. "1/16S, BT"
 Declination 4°25' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE May 8

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

