

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. Sec. R. <u>28</u> E. W.	K12
2. PROPERTY CONTROLLING IN SECTION _____	T. <u>41</u> N. Sec. R. <u>28</u> E. W.	10
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. Sec. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 23, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner K12 (1/4 corner between Sections 35 & 36, T41N, R28W):**  
 Sugar post (Not found. Found iron pipe S8½°E 63.7 ft.)  
 Sugar 8 S33W 9 (Not found. No subsequent accessory found.)  
 W. Pine 36 N53E 8 (Found. No subsequent accessory found)

**Corner 10 (South 1/16 corner between Sections 35 and 36, T41N, R28W):**  
 Not established in original survey and by approximation only, subsequently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner K12:** Re-monumented corner by reference to original BT indicated above, identified by species and size and remnant of notch at bottom of witness blaze. Iron pipe had been set erroneously by unknown parties on some unknown previous date.

**Corner 10:** Established on line between Sec. Cor. 1322.35 ft. S and 1/4 cor. 1322.35 ft. N. Found a 3" x 3" x 4' squared cedar post S32°E 14.2 ft. for an approximate corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for both corners:** 1" I.D. x 36" iron pipe with 3½" aluminum cap and 1/2" x 12" re-inforcing rod welded to bottom end.

**Witnesses for Corner K12:** Red Maple 9 S43°E (mag.) 47.3 ft. "1/4S, NBT"  
 Red Maple 6 S41°W (mag.) 35.5 ft. "1/4S, NBT"

**Witnesses for Corner 10:** Black Spruce 5 N49°E (mag.) 5.8 ft. "1/16S, BT"  
 Black Spruce 5 S27°W (mag.) 5.0 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 27, 1976  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

