

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. <u>XIX</u> S., R. <u>28</u> W.	L13
2. PROPERTY CONTROLLING IN SECTION _____	36, T. <u>41</u> N. <u>XIX</u> S., R. <u>28</u> W.	15
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 26, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner L13 (South 1/4 corner of Section 36, T41N, R28W):
 Cedar post (Not found. No subsequent monuments found.)
 Lynn 13 N68E 19 (" " " " accessories ")
 Sugar 12 N51 1/2 W 64 (" " " " " ")

Corner 15 (West 1/16 corner on South Line of Section 36, T41N, R28W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner L13: Re-established proportionately on line between Sec. Corners 2641.4 ft. to E and to W.

Corner 15: Established on line between Sec. Cor. 1320.7 ft. W and 1/4 cor. 1320.7 ft. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner L13: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap and 1/2"x12" re-inforcing rod welded to bottom end.

Sugar Maple 11 S65°W (mag.) 7.0 ft. "1/4S, NBT"

Sugar Maple 10 N81°E (mag.) 16.0 ft. "1/4S, NBT"

Sugar Maple 7 S15°E (mag.) 22.4 ft. "1/4S, NBT"

Corner 15: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.

Sugar Maple 7 N66°E (mag.) 15.6 ft. "1/16S, BT"

Ironwood 7 N36°W (mag.) 14.3 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 27, 1975
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

