

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>36</u>	T. <u>41</u> N. S., R. <u>28</u> <del>W.</del> <sup>W.</sup>	<u>#5, 5a, &amp; 5b</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner 5 (North 1/16 corner on N & S 1/4 line of Sec. 36, T41N, R28W):
- Corner 5a (North Aux. M.C. on N & S 1/4 line of Section 36):
- Corner 5b (South Aux. M.C. on N & S 1/4 line of Section 36):

None of these corners established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner 5: Established 6/27/75 on line between N 1/4 corner 1320.45 ft. N and Center 1/4 corner 1320.45 ft. S.
- Corner 5a: Established 6/27/75 on N. bank of Sturgeon River, about 5 ft. from water's edge, on line between Center 1/4 corner 865.0 ft. S and N 1/16 corner on N & S 1/4 line 455.45 ft. N.
- Corner 5b: Established 6/26/75 on S. bank of Sturgeon River, about 5 ft. from water's edge, on line between Center 1/4 corner 737.00 ft. S and N 1/16 corner on N & S 1/4 line 583.45 ft. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Monuments for all three corners: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap and 1/2" x 12" re-inforcing rod welded to bottom end.
- Witnesses for Corner 5: Cedar 8 N77°E (mag.) 32.3 ft. "1/16S, BT"  
Cedar 16 S64°E (mag.) 39.5 ft. "1/16S, BT"
- Witnesses for Corner 5a: South Aux. M.C. S0°21'05"W 128.0 ft.  
SW cor. of vertical corner molding on SW cor. of cottage S82°E (mag.) 44.4 ft.
- Witnesses for Corner 5b: Black Ash 6 S33°E (mag.) 38.8 ft. "AMC, BT"  
B. of Gilead 8 S38°W (mag.) 12.1 ft. "AMC, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 28, 1976

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

