

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> <sup>N.</sup> <sub>XX</sub> , R. <u>28</u> <sup>XX</sup> <sub>W.</sub>	L12
2. PROPERTY CONTROL- 36 ING IN SECTION_____	, T. <u>41</u> <sup>N.</sup> <sub>XX</sub> , R. <u>28</u> <sup>XX</sup> <sub>W.</sub>	12
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ <sup>N.</sup> <sub>S.</sub> , R. _____ <sup>E.</sup> <sub>W.</sub>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 26, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner L12 (Center of Section 36, T41N, R28W):**

Not established in original survey nor subsequently, apparently.

**Corner 12 (South 1/16 corner on N & S 1/4 line of Section 36, T41N, R28W):**

Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner L12:** Established at intersection of quarter-section lines.

**Corner 12:** Established on line between S 1/4 corner 1319.25 ft. S and Center 1/4 corner 1319.25 ft. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner L12:** 1" I.D. x 36" iron pipe with 3½" aluminum cap and ½"x12" re-inforcing rod welded to bottom end.

W. Spruce 6 S20°E (mag.) 7.2 ft. "1/4S, BT"

W. Spruce 12 S76°W (mag.) 27.4 ft. "1/4S, BT"

**Center 12:** 1" I.D. x 36" iron pipe with 3½" aluminum cap

Tamarack 6 S47°E (mag.) 5.6 ft. "1/16S, BT"

Cedar 5 S26°W (mag.) 51.0 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger  
MICHIGAN REGISTERED LAND SURVEYOR

DATE January 28, 1976

Arthur O. Enger  
Michigan Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 13581