

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> ^{N.} S. R. <u>28</u> ^{W.} E.	M13
2. PROPERTY CONTROLLING IN SECTION _____ 36	, T. <u>41</u> ^{N.} S. R. <u>28</u> ^{W.} E.	2
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} S. R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner M13 (Southeast Corner of Section 36, T41N, R28W):
 Cedar post (Not found. No subsequent monuments found.)
 Tamarack 6 N32E 20 (" " " " accessories ")
 Aspen 12 N86W 22 (" " " " " ")

Corner 2 (East 1/16 Corner between Sections 25 & 36, T41N, R28W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner M13: In 1959, B. D. Buckler re-established this position, as evidenced by corners proportioned from it on the range line north, but did not monument it. On 5/23/75, in keeping with Buckler's method, I re-monumented the corner at a position on the equal prolongation southward of his true line between the NE corner and E $\frac{1}{4}$ corner of Sec. 36.

Corner 2: Established 6/17/75, by traverse, on line between Sec. Cor. 1320.7 ft. E and 1/4 cor. 1320.7 ft. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M13: 1" I.D. x 36" iron pipe with 3 $\frac{1}{2}$ " aluminum cap.
 Cedar 8 S24^oW (mag.) 33.4 ft. "S3, NBT"
 Cedar 5 N53^oE (mag.) 16.2 ft. "S31, NBT"
 Cedar 5 N34^oW (mag.) 43.8 ft. "S36, NBT"

Corner 2: 1" I.D. x 36" iron pipe with 3 $\frac{1}{2}$ " aluminum cap and $\frac{1}{2}$ "x12" reinforcing rod welded to bottom end.
 W. Spruce 10 N74^oE (mag.) 21.6 ft. "1/16S, BT"
 W. Spruce 7 S43 $\frac{1}{2}$ ^oW (mag.) 26.4 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 28, 1976

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

