

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41 NR. 28 W. . .

----- DICKINSON ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 25, 26, 35, 36 .

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap. -----

WITNESSES TO CORNER ----- 12" Red Pine S 26° E 23 links. -----

----- 10" Red Pine N 14° W 51 links. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

One (probable B.T.) White Pine stump badly rotted.

This location puts the Section Corner 1 link north and 2 links east of
a point established by Double Proportionate Measurement. Good corners
1/2 mile east; 1/2 mile north; 1 mile south; and 2 miles west.

Corner placed and witnessed July 12, 1955.

SURVEYORS SEAL

SIGNED

Billy D. Buckler

REGISTERED LAND SURVEYOR

DATE 1/26/56