

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 41. NR. 28. W. . .

DICKINSON

COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 16, 17, 20, 21

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap.

WITNESSES TO CORNER 12" Ironwood S 26° E 20 links.

12" Sugar Maple N 52° W 80 links.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

Section Corner set by Double Proportionate Measurement North, South,  
and East to stream; West to 1/4 Corner 1/2 mile. One Sugar Maple,  
probable B. T. in place.

Corner placed and witnessed July 13, 1955.

SURVEYORS SEAL

SIGNED

*Billy D. Buckles*

REGISTERED LAND SURVEYOR

DATE 1/23/56