

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41. NR. 28. W. . .

----- DICKINSON ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 20, 21, 28, 29.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap.

WITNESSES TO CORNER 9" White Birch N 25° W 16 links.

8" White Birch S 10° E 32 links.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Section Corner set by Double Proportionate Measurement from good corners; 1/2 mile East, 1 mile North, 1 mile West, and 1/2 mile South. No evidence of original corner.

Corner placed and witnessed July 15, 1955.

SURVEYORS SEAL

SIGNED

Billy D. Buckler

REGISTERED LAND SURVEYOR

DATE 1/23/56