

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41 NR 28 W . .

----- DICKINSON ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19, 20, 29, 30

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap.

WITNESSES TO CORNER 10" Red Oak S 85° E 71 links.

8" Aspen N 58° W 61 links.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Section Corner has been set by unknown surveyor.

1" iron pipe in place. No evidence of original B. T.'s.

Section Corner is 16 links West and 10 links South of a point arrived
at by Double Proportionate Measurement, from Corners, North, South,
East, and West.

Corner placed and witnessed July 15, 1955.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 1/23/56
REGISTERED LAND SURVEYOR