

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41. NR. 28 W. .

----- DICKINSON ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 23, 24, 25, 26.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap. -----

WITNESSES TO CORNER 8" Elm ----- N 61° W 80 links. -----

24" White Pine Stump S 1° E 28 links. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Section Corner set by Double Proportionate Measurement from four directions. East, South, West to good Corners. North to top of hill. No evidence of original corner.

Corner placed and witnessed July 25, 1955.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 1/26/56
REGISTERED LAND SURVEYOR