

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 41 NR. 28-29 W

Dickinson

COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 7-12

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 24" Cedar N 71° W 80 links

"1/4 S NBT"

15" Cedar S 33° W 11 links

"1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 corner from one cedar B.T. bearing N 57° W 35 links in poor condition(down). Scribe marks visible, and one cedar B.T. bearing S 44° E 12 links in poor condition. Found notch in remains.

Found magnetic compass somewhat erratic in this area.

Found by Forestry Division Survey crew.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 8/2/57  
REGISTERED LAND SURVEYOR