

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(DICKINSON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> N. <u>28</u> E. R. <u>28</u> W.	<u>A-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>6</u>	T. <u>41</u> N. <u>28</u> E. R. <u>28</u> W.	<u>10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner A2 (1/4 corner between Sections 1 & 6, T41N, R28-29W):
    - B. Ash post (Not found. No subsequent monuments found.)
    - B. Ash 7 S50E 17 (" " " " accessories " .)
    - Cedar 7 N56W 13 (" " " " " " .)
  - Corner 10 (South 1/16 corner between Sections 1 & 6, T41N, R28-29W):  
Not established in original survey nor subsequently, apparently.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner A2: Restored 5/19/78 on line between Sec. Cor. 39.862 ch. to N and to S.
  - Corner 10: Established 5/22/78 on line between Sec. Cor. 19.931 ch. S and 1/4 Corner 19.931 ch. N.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner A2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
Cedar 13 S80 E (mag.) 25.3 ft. "1/4S,NBT"  
B. Ash 15 N15 E (mag.) 30.6 ft. "1/4S,NBT"  
Declination is 0 40' East.
  - Corner 10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
B. Spruce 10 N41 E (mag.) 2.5 ft. "1/16S,BT"  
Cedar 10 S16 W (mag.) 47.3 ft. "1/16S,BT"  
Declination is 1 50' East.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY MICHIGAN REGISTERED LAND SURVEYOR DATE August 14, 1978

Arthur O. Enger  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

