

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. K , R. 28 K W.	D-1
2. PROPERTY CONTROLLING IN SECTION	5, T. 41 N. K , R. 28 K W.	1
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D1 (1/4 corner between Sections 5 & 32, T41-42N, R28W):
 Spruce 5 for corner (Not found. No subsequent monuments found.)
 W. Pine 4 N45W 2 (Not found. No subsequent accessories found.)

Corner 1 (West 1/16 corner between Sections 5 & 32, T41-42N, R28W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D1: Restored 9/1/77 on line between Sec. Corners N89°39.5'E 40.1475 ch. and 589°39.5'W 40.1475 ch. Corner is on S face of a granite ridge.

Corner 1: Established 6/28/78 on line between Sec. Cor. 20.074 ch. W and 1/4 cor. 20.074 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Pine 12 S86°W (mag.) 19.4 ft. "1/4S, NBT"
 Red Pine 8 N34°E (mag.) 3.8 ft. "1/4S, NBT"
 Declination is 0°50' West. Also squared & scribed a 4" red pine, N34°E 1.5 ft. (to center).

Corner 1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Cedar 7 N80°W (mag.) 17.8 ft. "1/16S, BT"
 Cedar 7 S 5°W (mag.) 4.4 ft. "1/16S, BT"
 Declination is 1°10' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 19, 1978

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

