

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(DICKINSON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 41 N. S. R. 28 E. <input checked="" type="checkbox"/> W.	C-2
2. PROPERTY CONTROLLING IN SECTION _____	6, T. 41 N. S. R. 28 E. <input checked="" type="checkbox"/> W.	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S. R. _____ E. <input checked="" type="checkbox"/> W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C2 (1/4 corner between Sections 5 & 6, T41N, R28W):
 Cedar post (Not found. No subsequent monuments found.)
 Hemlock 18 S51E 9 (Not found. No subsequent accessories found.)
 Y. Birch 20 N42W 12 (Not found. No subsequent accessories found.)

Corner 14 (South 1/16 corner between Sections 5 & 6, T41N, R28W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C2: Restored 3/13/78 proportionately on line between Sec. Cor. 39.586 ch. S and Sec. Cor. 39.786 ch. N.
Corner 14: Established 6/29/78 on line between Sec. Cor. 19.793 ch. S and 1/4 cor. 19.793 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 10 (smaller of twins) N53°E (mag.) 17.7 ft. "1/4S, NBT"
 W. Pine 4 N26°W (mag.) 24.9 ft. "1/4S, NBT"
 Declination is 2°30' West.

Corner 14: ⊕ chiselled on a rock outcrop oriented E & W.
 White Pine 4 N55°E (mag.) 6.9 ft. "1/16S, BT"
 Red Maple 8 S 8°W (mag.) 26.5 ft. "1/16S, BT"
 Declination is 3°00' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE Aug 11 1978
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

