

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. <u>X</u> , R. <u>28</u> W. <u>X</u>	F-1
2. PROPERTY CONTROLLING IN SECTION <u>5</u>	, T. <u>41</u> N. <u>X</u> , R. <u>28</u> W. <u>X</u>	7
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner F1 (1/4 corner between Sections 4 & 33, T41-42N, R28W):**  
 W. Pine 30 for Corner Tree (Probably found. Found 1 1/2" I.D. iron pipe.)  
 W. Pine 6 N63E 17 (Not found. No subsequent accessories found.)  
 Aspen 6 N45W 40 (Not found. No subsequent accessories found.)

**Corner 7 (North 1/16 corner between Sections 4 & 5, T41N, R28W):**  
 Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner F1:** On 9/1/77 witnessed a 1 1/2" I.D. iron pipe found in the apparent up-turned roots of a large W. Pine, well-rotted and lying beneath the forest duff in a NNW direction. Original corner tree was a W. Pine 30 and this is presumed to be its remains, as it is consistent with corners to W and natural features called for in original notes to W and E. Pipe has been in place for a long time and has a steel cap stamped "41 & 42, 33-4, R28." Probably set by W. C. Johnson of Dickinson Co. Rd. Comm. in 1936.  
**Corner 7:** Established 6/16/78 proportionately on line between 1/4 cor. 19.8115 ch. S and Sec. Cor. 20.109 ch. N. Corner in swamp.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner F1:** 1 1/2" I.D. iron pipe (length unknown) with steel pipe cap.  
 Cedar 7 N16°W (mag.) 18.3 ft. "1/4S, NBT"  
 Cedar 8 S83°W (mag.) 16.7 ft. "1/4S, NBT"  
 Declination is 2°50' West.

**Corner 7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 B. Ash 6 N65°W (mag.) 17.3 ft. "1/16S, BT"  
 B. Ash 6 N19°E (mag.) 8.5 ft. "1/16S, BT"  
 Declination is 3°20' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1978

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

