

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(DICKINSON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 28 K. W.	C-6
2. PROPERTY CONTROLLING IN SECTION	7, T. 41 N. R. 28 K. W.	16
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C6 (1/4 corner between Sections 17 & 18, T41N, R28W):
 Elm post (Not found. See B for subsequent monument.)
 Sugar 16 N52E 3 (Not found. No subsequent accessories found.)
 Sugar 8 S48W 37 (Not found. No subsequent accessories found.)

Corner 16 (East 1/16 corner between Sections 7 & 18, T41N, R28W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: Corner C6: Restored 3/22/77 on line between Sec. Cor. S0°09.5' E 39.411 ch. and Sec. Cor. N0°09.5' W 40.000 ch. As this section line was found to be short as compared to the original record distance, a question of distribution of the shortage arose. By comparing actual distances found to a swamp edge S of this corner, it appears that the bulk of the shortage probably occurs in the south 1/2-mile, while the north 1/2-mile is about regular. Being unable to be more specific than that, the north 1/2-mile was made an even 40.00 ch., while the remainder of the total distance was put in the south 1/2-mile. Found a 3/4" I.D. iron pipe N76°15.2' W 79.90 ft. as placed by unknown persons from unknown evidence (probably none) to represent this corner. Corner 16: Established 11/4/77 on line between Sec. Cor. 20.012 ch. E and 1/4 cor. 20.012 ch. W. Corner falls just off S edge of Calumet Mine Road as existing on this date.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C6: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 Sugar Maple 8 N46°W (mag.) 3.7 ft. "1/4S, NBT"
 Sugar Maple 7 S10 1/2°E (mag.) 6.4 ft. "1/4S, NBT"
 Declination 3°45' East.

Corner 16: 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 8 N44°E (mag.) 84.2 ft. "1/16S, BT"
 Cedar 7 N61°W (mag.) 78.8 ft. "1/16S, BT"
 Declination 4°30' West. Note: Monument is buried with top about 1 1/2 ft. below ground surface. A 3" x 3" x 5' square, scribed cedar post was set directly over it.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE Aug 78

CHIEF OF SURVEY PART
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 13581