

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	(DICKINSON COUNTY) LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 28 W.	E-2
2. PROPERTY CONTROLLING IN SECTION	5, T. 41 N. R. 28 W.	9 & 14
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 9, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner E2 (1/4 corner between Sections 4 & 5, T41N, R28W):
 Y. Birch post (Not found. Found a rotted cedar post.)
 Hemlock 20 S66W 11 (Not found. No subsequent accessories found.)
 Cedar 10 N63E 14 (Not found. No subsequent accessories found.)

**Corner 9 (East 1/16 corner on E & W 1/4 line, Section 5, T41N, R28W) and
 Corner 14 (South 1/16 corner between Sections 4 & 5, T41N, R28W):**
 Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner E2: Replaced old, down cedar post with monument described below.
 Position agrees closely with ridges to N & S called for in original field notes.
 Corner bears N0°03.9' W 39.7465 ch. from Sec. Cor. to S and S0°00.2' E 39.920 ch. from Sec. Cor. to N, which is nearly proportionately on line between them.
Corner 9: Established on E & W 1/4 line between Center 1/4 cor. 20.0445 ch. W and E 1/4 cor. 20.0445 ch. E.

Corner 14: Established on line between Sec. Cor. 19.873 ch. S and 1/4 cor. 19.873 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner E2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 9 N70°W (mag.) 28.7 ft. "1/4S, NBT"
 Sugar Maple 7 N68°E (mag.) 21.3 ft. "1/4S, NBT" (Declination is 5°30' West)
Corner 9: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap, set in rock mound.
 Cedar 6 N69°E (mag.) 8.7 ft. "1/16S, BT"
 Cedar 6 S72°W (mag.) 5.5 ft. "1/16S, BT"
 Declination is 2°40' West. Also squared and scribed an 8" cedar S71°E 0.9 ft. (to center)
Corner 14: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Cedar 7 N73°W (mag.) 10.8 ft. "1/16S, BT":
 Cedar 6 N60°E (mag.) 5.0 ft. "1/16S, BT"
 Declination is 6°50' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 10, 1978
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

