

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	(DICKINSON COUNTY) LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 41 ^{N.} S. , R. 28 ^{K.} W.	D-3
2. PROPERTY CONTROLLING IN SECTION _____	5, T. 41 ^{N.} S. , R. 28 ^{K.} W.	12 & 15
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, ^{N.} S. , R. _____, ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 27, 1978, established re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D3 (1/4 corner between Sections 5 & 8, T41N, R28W):
 Maple post (Not found. See B for approx. cor. monument.)
 Hemlock 8 S36W 30 (Not found. No subsequent accessories found.)
 Cedar 12 N44E 25 (Not found. No subsequent accessories found.)

Corner 12 (South 1/16 corner on N & S 1/4 line, Section 5, T41N, R28W) and

Corner 15 (West 1/16 corner between Sections 5 & 8, T41N, R28W):
 Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D3: Restored at intersection of true line from monument at 1/4 cor. 8 & 17 extended N'y through a mon. purporting to be the Center of Sec. 8 to the reestablished true sec. line bet. 5 & 8. The latter line is thus divided into a west half measuring 40.060 ch. and an east half measuring 40.066 ch., very nearly equal. Found a 3" x 3" x 3' squared cedar post N33°E 20.2 ft. for a forester's approx. corner.

Corner 12: Established on line between S 1/4 cor. 19.834 ch. S and Center 1/4 cor. 19.834 ch. N.

Corner 15: Established on line between 1/4 cor. 20.030 ch. E and Sec. Cor. 20.030 ch. W. Corner falls in west rut of a NW & SE woods road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

White Pine 16 N54°W (mag.) 65.3 ft. "1/4S, NBT"

Red Maple 12 N67°E (mag.) 21.8 ft. "1/4S, NBT"

Declination is 5°50' West.

Corner 12: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

White Spruce 8 N16°W (mag.) 14.6 ft. "1/16S, BT"

Red Pine 4 S75°E (mag.) 20.5 ft. "1/16S, BT" (Declination is 5°00' West.)

Corner 15: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

Red Pine 27 N37°E (mag.) 11.6 ft. "1/16S, BT"

Cedar 11 S 4°W (mag.) 43.5 ft. "1/16S, BT"

Declination is 6°20' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 10 1978
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

