

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. 28 <del>X</del> E. R. 28 W.	E-1
2. PROPERTY CONTROLLING IN SECTION	5, T. 41 N. 28 <del>K</del> E. R. 28 W.	2 & 5
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner E1 (Section Corner 4, 5, 32, & 33, T41-42N, R28W):

- Cedar post (Not found. No subsequent monuments found.)
- W. Birch 8 N49W 6 (Not found. No subsequent accessories found.)
- W. Birch 6 N16E 13 (Not found. No subsequent accessories found.)

Corner 2 (East 1/16 corner between Sections 5 & 32, T41-42N, R28W) and

Corner 5 (North 1/16 corner on N & S 1/4 line, Section 5, T41N, R28W):

Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E1: Restored 9/1/77 proportionately on line between 1/4 cor. N89°39.5' E 40.148 ch. and Sec. Cor. S89°39.5' W 80.295 ch. Found a 10" cedar blazed on 4 sides S76°W 20.9 ft. for an approx. corner.

Corner 2: Established 6/28/78 on line between Sec. Cor. 20.074 ch. E and 1/4 cor. 20.074 ch. W.

Corner 5: Established 6/28/78 proportionately on line between Center 1/4 cor. 19.800 ch. S and N 1/4 cor. 20.047 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

- Cedar 12 S36°W (mag.) 17.1 ft. "S 4, NBT"
- Cedar 9 N53°E (mag.) 20.0 ft. "S33, NBT"
- Cedar 9 N15°W (mag.) 18.9 ft. "S32, NBT" (Declination is 1°30' West.)

Corner 2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

- Cedar 5 N36°W (mag.) 10.9 ft. "1/16S, BT"
- Cedar 5 S58°W (mag.) 20.7 ft. "1/16S, BT" (Declination is 0°20' West.)

Corner 5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

- Cedar 14 S14°E (mag.) 28.1 ft. "1/16S, BT"
- Cedar 8 S81°W (mag.) 37.0 ft. "1/16S, BT"

Declination is 2°10' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 10, 1978

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

