

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. 28 W. R. 28 X.	B-1
2. PROPERTY CONTROLLING IN SECTION	6 T. 41 N. 28 W. R. 28 X.	1 & 2
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner B1 (1/4 corner between Sections 6 & 31, T41-42N, R28W):
 Hemlock post (Not found. No subsequent monuments found.)
 Y. Birch 16 N45W 1 (Not found. No subsequent accessories found.)
 Hemlock 12 N35E 34 (Not found. No subsequent accessories found.)

Corner 1 (West 1/16 corner between Sections 6 & 31, T41-42N, R28W) and
Corner 2 (East 1/16 corner between Sections 6 & 31, T41-42N, R28W):
 Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner B1: Restored 11/17/77 proportionately on line between Sec. Cor. 40.387 ch. E and Sec. Cor. 40.468 ch. W.

Corner 1: Established 11/17/77 proportionately on line between 1/4 cor. 20.194 ch. E and Sec. Cor. 20.274 ch. W.

Corner 2: Established 11/14/77 on line between Sec. Cor. 20.194 ch. E (19.921 ch. from Witness Corner for this Sec. Cor.) and 1/4 cor. 20.194 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner B1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 10 S14°W (mag.) 11.8 ft. "1/4S, NBT"
 Cedar 8 N51°E (mag.) 39.5 ft. "1/4S, NBT"

Note: Distances are horizontal. Declination is 1°00' West.

Corner 1: Ⓢ Chiselled in a rock outcrop for the corner, with a 7" cedar squared and scribed for a guard post, S20°E 5.2 ft. (to center of tree).
 Cedar 8 S69°E (mag.) 22.2 ft. "1/16S, BT"
 Cedar 7 S38°W (mag.) 23.4 ft. "1/16S, BT" (Declination is 0°30' West)

Corner 2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Cedar 22 N23 1/2°W (mag.) 48.7 ft. "1/16S, BT" (Distances horizontal.
 Cedar 8 S14°W (mag.) 13.3 ft. "1/16S, BT" Declination is 1°10' West)

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 10, 1978
 CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

