

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---------------------------------------|---------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 41 N. 28 W. S. | C-1 |
| 2. PROPERTY CONTROLLING IN SECTION | 6, T. 41 N. 28 W. S. | 7 |
| 3. MISCELLANEOUS PROPERTY IN SECTION | , T. N. S., R. E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on_____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C1 (Section Corner 5, 6, 31, & 32, T41-42N, R28W):
 Cedar post (Not found. No subsequent monuments found.)
 Cedar 16 N62W 70 (Not found. No subsequent accessories found.)
 Cedar 14 S69W 61 (Not found. No subsequent accessories found.)
 Cedar 16 S71W 62 (Not found. No subsequent accessories found.)

Corner 7 (North 1/16 corner between Sections 5 & 6, T41N, R28W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner C1: Restored 11/14/77, at a position determined by measurements based on the original random line notes from streams to N, E, and S, with which the measurements agree almost exactly. The corner falls in a recent sub-channel of the west branch of Sturgeon River, formed since the original survey. Although a monument, described below, was placed at the true corner, its stability is questionable; therefore another monument was placed on the sec. line N89°21.3' W 18.02 ft. for a witness corner.

Corner 7: Established 3/13/78 proportionately on line between Sec. Cor. 19.992 ch. N and 1/4 cor. 19.794 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner C1: 1" I.D. x 42" iron pipe with 3 1/2" aluminum cap at true corner in stream.
 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap for witness corner.
 New Bearing Trees are for the Witness Corner monument.

Cedar 20 N43°W (mag.) 12.9 ft. "WC, BT"
 Cedar 13 S68°W (mag.) 15.9 ft. "WC, BT"
 B. Ash 14 S12°E (mag.) 5.3 ft. "WC, BT"

Declination is 1°10' West.

Corner 7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 5 N44 1/2°W (mag.) 38.4 ft. "1/16S, BT"
 Sugar Maple 8 S30°W (mag.) 34.2 ft. "1/16S, BT"

Declination is 1°45' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 14, 1978
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

