

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --	(DICKINSON COUNTY) LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> N. R. <u>28</u> E. W.	A-8
2. PROPERTY CONTROLLING IN SECTION	<u>19</u> , T. <u>41</u> N. R. <u>28</u> E. W.	3 & 10
3. MISCELLANEOUS PROPERTY IN SECTION	_____, T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner A8 (1/4 corner between Sections 19 & 24, T41N, R28-29W):
    - Cedar post (Not found. No subsequent monuments found.)
    - Pine 18 N25E 45 ( " " " " accessories " .)
    - Fir 7 S70W 38 ( " " " " " " .)
  - Corner 3 (North 1/16 corner between Section 19 & 24, T41N, R28-29W) and
  - Corner 10 (South 1/16 corner between Sections 19 & 24, T41N, R28-29W):  
Neither of these corners established in original survey nor subsequently, apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner A8: Restored 11/8/77 on line between Sec. Corners 39.902 Ch. to N and to S.
  - Corner 3: Established 11/8/77 on line between Sec. Cor. 19.951 ch. N and 1/4 cor. 19.951 ch. S.
  - Corner 10: Established 7/12/78 on line between Sec. Cor. 19.951 ch. S and 1/4 cor. 19.951 ch. N.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner A8: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
    - White spruce 12 S54 E (mag.) 21.9 ft. "1/4S,NBT"
    - Red Maple 6 N 1/2 E (mag.) 20.7 ft. "1/4S,NBT"
    - Declination is 0 05' West.
  - Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
    - Sugar Maple 8 S86 E (mag.) 19.7 ft. "1/16S,BT"
    - Red Pine 22 N25 W (mag.) 30.5 ft. "1/16S,BT"
    - Declination is 0 55' East
  - Corner 10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
    - B. Ash 6 S61 E (mag.) 18.0 ft. "1/16S,BT"
    - B. Ash 5 N7 W (mag.) 10.2 ft. "1/16S,BT" Declination is 0 30' West.)

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 15 1978  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
 Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

