

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	(Dickinson County) LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ E. _____ S., R. _____ W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>7</u>	T. <u>41</u> N. <u>28</u> E. <u>X</u> <del>S</del> R. <u>28</u> W.	9 & 14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S., R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner 9** (East 1/16 corner on E & W 1/4 line of Section 7, T41N, R28W) and

**Corner 14** (South 1/16 corner between Sections 7 & 8, T41N, R28W):

Neither of these corners established in original survey. At Corner 14 found an iron pipe at the base of a 12" ironwood tree, purporting to be this corner, at a point S37°28.1E 66.52 ft. from corner reported herein. My measurements of this section line indicate no way to justify its existence at that point.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner 9:** Established 11/2/77 on E & W 1/4 line 20.033 ch.W of E 1/4 cor. and 20.033 ch. E of Center 1/4 cor. Found a 3" x 3" x 4 1/2' squared cedar post S84°E 61.0 ft. for an approx. corner.

**Corner 14:** Established 9/30/77 on line between Sec. Cor. 20.007 ch. S and 1/4 corner 20.007 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner 9:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
B. Spruce 8 S52°E (mag.) 25.7 ft. "1/16S, BT"  
Cedar 11 N49°E (mag.) 51.1 ft. "1/16S, BT"  
Declination is 4°45' East.

**Corner 14:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
Sugar Maple 6 N16°W (mag.) 9.0 ft. "1/16S, BT"  
Sugar Maple 10 S76°W (mag.) 22.0 ft. "1/16S, BT"  
Declination is 4°10' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE August 12, 1978  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

