

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> N. <u>X</u> , R. <u>28</u> E. <u>W.</u>	<u>A-3</u>
2. PROPERTY CONTROLLING IN SECTION <u>7</u>	, T. <u>41</u> N. <u>X</u> , R. <u>28</u> E. <u>W.</u>	<u>3</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. <u>W.</u>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 22, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A-3 (Section Corner 1, 6, 7, & 12, T41N, R28-29W):

Cedar post (Not found. No subsequent monuments found)
 Hemlock 14 S76E 30 (" " " " accessories " .)
 Hemlock 8 N65W 17 (" " " " " " .)

Corner 3 (North 1/16 corner between Sections 7 & 12, T41N, R28-29W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A-3: Restored on line between 1/4 cor. 39.862 ch. S and Sec. Cor. 79.723 ch. N.
 Corner falls on top of a 40 ft. E & W granite ridge.

Corner 3: Established on line between 1/4 cor. 19.931 ch. S and Sec. Cor. 19.931 ch. N.
 Corner falls in a small black ash swale.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A-3: ● chiselled in bedrock with a 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap set over it in a mound of rocks.

Red Pine 12 S61°W (mag.) 11.9 ft. "S12,NBT"
 Red Pine 13 N2 1/2°E (mag.) 28.6 ft. "S6,NBT"

Declination is 3°00' East.

Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap, set in rock mound.

Red Maple 5 N71 1/2°W (mag.) 24.7 ft. "1/16S,BT"
 Red Maple 3 S81°E (mag.) 18.0 ft. "1/16S,BT"

Declination is 5°00' East. Also squared & scribed a 3" B. Ash S82°E 5.0 ft. (to center)

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE Aug 17, 1978

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

13581

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

