

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> ^{N.} / _{X.} , R. <u>28</u> ^{X.} / _{W.}	<u>A-6</u>
2. PROPERTY CONTROLLING IN SECTION <u>18</u>	T. <u>41</u> ^{N.} / _{X.} , R. <u>28</u> ^{X.} / _{W.}	<u>3</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} / _{S.} , R. _____ ^{E.} / _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____	_____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A6 (1/4 corner between Sections 13 & 18, T41N, R28-29W):
 Sugar Maple post (Not found. No subsequent monuments found.)
 Hemlock 20 N45 1/2W 16 (" " " " accessories " .)
 Hemlock 18 S53 1/2E 45 (" " " " " " .)

Corner 3 (North 1/16 corner between Sections 13 & 18, T41N, R28-29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A6: Restored 11/4/77 on line between Sec. Cor. 39.933 ch. to N and to S.
Corner 3: Established 11/8/77 on line between Sec. Cor 19.966 ch. N and 1/4 cor. 19.966 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A6: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Sugar Maple 11 S65°W (mag.) 27.3 ft. "1/4S, NBT"
 Sugar Maple 6 N74°E (mag.) 29.0 ft. "1/4S, NBT"
 Declination is 5°55' East

Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 W. Spruce 7 S71°W (mag.) 11.8 ft. "1/16S, BT"
 Elm 5 S29 1/2°E (mag.) 28.3 ft. "1/16S, BT"
 Declination is 8°20' East

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 15, 1978
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources
 SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

