

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. <u>2.</u> R. <u>28</u> E. <u>0.</u>	<u>B-4</u>
2. PROPERTY CONTROLLING IN SECTION <u>7</u>	T. <u>41</u> N. <u>2.</u> R. <u>28</u> E. <u>0.</u>	<u>8</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 4, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A Description of original monument and accessories and/or subsequent restoration:

Corner B4 (Center of Section 7, T41N, R28W) and

Corner 8 (West 1/16 corner on E & W 1/4 line of Section 7, T41N, R28W):

Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner B4: Established at computed intersection of quarter-section lines, from a reference transit line between the E 1/4 cor. and W 1/4 cor. of the section. The computations were derived from a closed traverse around the perimeter of Sec. 7.

Corner 8: Established proportionately on the E & W 1/4 line between the center 1/4 cor. 20.033 ch. E and the W 1/4 cor. 20.927 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner B4: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 W. Spruce 11 N68°E (mag.) 20.6 ft. "1/4S, BT"
 W. Spruce 7 N12°W (mag.) 12.3 ft. "1/4S, BT"
 Declination is 1°30' East

Corner 8: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 W. Pine 20 N54°W (mag.) 42.8 ft. "1/6S, BT"
 W. Pine 24 N65°E (mag.) 49.3 ft. "1/16S, BT"
 Declination is 2°45' East

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 15, 1978

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

