

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. R. <u>28</u> K. W.	<u>C-4</u>
2. PROPERTY CONTROLLING IN SECTION <u>7</u>	T. <u>41</u> N. R. <u>28</u> K. W.	<u>7</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C4 (1/4 corner between Sections 7 & 8, T41N, R28W):
 Y. Birch post (Not found. No subsequent monuments found.)
 Y. Birch 12 N50E 8 (" " " " accessories ")
 Cedar 14 S30W 22 (" " " " " ")

Corner 7 (North 1/16 corner between Sections 7 & 8, T41N, R28W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C4: Restored 9/1/77 on line between Sec. Corners 40.014 ch. to N and to S. Corner falls on high ground, about 1 chain S of a swamp edge, as mentioned in original field notes.

Corner 7: Established 6/29/78 on line between Sec. Cor. 20.007 ch. N and 1/4 cor. 20.007 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C4: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Cedar 16 S74°W (mag.) 66.1 ft. "1/4S,NBT"
 Cedar 8 N7°W (mag.) 37.0 ft. "1/4S,NBT"
 Distances are horizontal. Delineation is 4°50' West.

Corner 7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 W. Spruce 10 N56°W (mag.) 18.0 ft. "1/16S,BT"
 W. Spruce 6 S64°E (mag.) 18.0 ft. "1/16S,BT"
 Declination is 2°50' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 14 1978
CHIEF OF SURVEY ARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

