

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> N. R. <u>28</u> E. W.	<u>A-1</u>
2. PROPERTY CONTROLLING IN SECTION	<u>6</u> , T. <u>41</u> N. R. <u>28</u> E. W.	<u>3</u>
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A1 (Section Corner 1, 6, 31, & 36, T41-42N, R28-29W):

Wood post	(Not found. No subsequent monuments found.)
Y. Birch 18 N27W 7	(" " " " accessories ")
Hemlock 8 S50 E 25	(" " " " " " ")

Corner 3 (North 1/16 corner between Sections 1 & 6, T41N, R28-29W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A1: Restored 11/14/77 on true line extended S'ly from mon. at Sec. Cor. 25, 30, 31, & 36, T42N, R28-29W through 1/4 cor. bet. Sec. 31 & 36, T42N, R28-29W a distance equal to twice the measured distance between those two corners, the original field notes stating the distance to be thus. Corner as set bears S0°22'20"W 79.874 ch. from 25,30,31,& 36 and N0°04'40" E 119.581 ch. from original 1/4 cor. bet. 7 & 12, T41N, R28-29W, which is an entirely reasonable relationship according to my extensive retracement surveys in Sec. 5, 6, 7, & 8 of this township.

Corner 3: Established 5/19/78 on line between Sec. Cor. 19.931 ch. N and 1/4 cor. 19.931 ch.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A1: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap

Sugar Maple 6 S49°E (mag.)	23.2 ft. "S6,NBT"
Sugar Maple 6 N20°E (mag.)	9.8 ft. "S31,NBT"
Sugar Maple 6 N38°W (mag.)	16.2 ft. "S36,NBT"

Declination is 0°25' West.

Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap

White Spruce 8 S59°E (mag.)	22.1 ft. "1/16S,BT"
Red Maple 14 N17°W (mag.)	32.0 ft. "1/16S,BT"

Declination is 0°20' East.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 12, 1978

CHIEF OF SURVEY PARTY

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

