

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(DICKINSON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 28 W.	E-3
2. PROPERTY CONTROLLING IN SECTION	5, T. 41 N. R. 28 W.	16
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. R. E. S. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E3 (Section Corner 4, 5, 8, & 9, T41N, R28W):

Cedar post	(Not found. Found 1 1/8" I.D. x 36" iron pipe).
Tamarack 12 S31W 10	(Not found. No subsequent accessories found).
Cedar 8 N22E 12	(Not found. No subsequent accessories found).

Corner 16 (East 1/16 corner between Sections 5 & 8, T41N, R28W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E3: On 6/16/78 replaced the found iron pipe with new monument shown below. Pipe had been placed by W. C. Johnson et al., Dickinson County Road Commission, on 1/15/36. Johnson's notes say, "Found squared hemlock stake set by Slater 1926--planted flanged pipe." I found no original evidence, but Slater, an early 20th century timber cruiser, was usually quite accurate in his monumentations. Corner checks well with swamp edges to N, W, and S.

Corner 16: Established 5/9/78 on line between Sec. Cor. 20.033 ch. E and 1/4 cor. 20.033 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap

Cedar 10 S71°E (mag.) 21.4 ft.	"S9, NBT"
Cedar 8 S47°W (mag.) 15.0 ft.	"S8, NBT"
Cedar 7 N39°W (mag.) 10.6 ft.	"S5, NBT"

Declination is 8°00' West.

Corner 16: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap

B. Spruce 9 N41°W (mag.) 14.0 ft.	"1/16S, BT"
B. Spruce 8 S32°W (mag.) 22.3 ft.	"1/16S, BT"

Declination is 5°45' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

