

Common to T41 R29 W

A-6 ✓
A-7

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12:25

For corners in

<u>Dickinson</u> (County) <u>Sagola Twp.</u>	Located in:	Corner Code #
1. Public Land Survey	T41NR 30W	M-6
	T R	M-7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS
LACKENBERRY COUNTY

SURVEY &
REMONUMENTATION

NOV 15 1998

SECTION Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert F. Perkins, in a field survey on Nov. 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-6 East 1/2 Corner, Section 13
Post by Wm. A. Burt, D.S. 1846
Original Bearing Trees
W. Pine 16" S59°W 6 Lk.
Y. Pine 18" N31°E 15 Lk.

M-7 Southeast Corner, Section 13
Post by Wm. A. Burt, D.S. 1846
Original Bearing Trees:
Tamarack 11" S49°W 17 Lk.
Tamarack 10" N12°E 21 Lk.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found 1" Iron Pipe Marker with 4" Brass Cap Set from G.L.O. BT by D.C. DeLaMater, RLS 10-28-1953.
1953 Bearing Trees:
J. Pine 14" S35°W 61 Lk.
W. Pine 26" S43°E 227 Lk.

M-7 No Evidence of Original Corner or its Accessories Found.
Found 1" Pipe Marker with 4" D.N.R. Brass Cap Set by D.C. DeLaMater, RLS 10-23-1953 (Old Corner Report #112)
1953 Bearing Trees:
Spruce 12" S27°W 47 Lk. (Found)
Cedar 18" S13°E 72 Lk. (Found)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Found and Accepted Pipe Marker described in "B" above:
New Witnesses:
Spruce 11" S30°W(M.B.) 25.70' Nail/Tag
W. Pine 3" S42°E(M.B.) 18.05' Nail/Tag
Dbl. Maple 8" N84°E(M.B.) 24.42' Nail/Tag
Maple 5" N15°W(M.B.) 26.05' Nail/Tag
Placed Carsonite Marker 0.80' West.

M-7 Found and Accepted Pipe Marker described in "B" above.
New Witnesses:
Spruce 10" N45°W(M.B.) 43.15' Nail/Tag
Spruce 10" S74°W(M.B.) 33.78' Nail/Tag
Spruce 14" S27°W(M.B.) 31.02' Nail/Tag
Cedar 24" S13°E(M.B.) 47.52' Nail/Tag
Placed Carsonite Marker 0.40' West.

Signed by Robert F. Perkins
Surveyor's Michigan License No. 12027

Date Nov. 20, 1998

