

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 1999 NOV 30 PM 3:31

For corners in

DICKINSON Located In: Corner Code #
 (County)

NORWAY TOWNSHIP

1. Public Land Survey T 41 N R 29 W C-10
 T R
 T R SURVEY &
 T R REESTABLISHMENT

2. Property Controlling S T R
 in Section S T R MAR 24 2000

3. Miscellaneous S T R
 Property in Sec. S T R

SECTION

REGISTER OF DEEDS
 DICKINSON COUNTY
 RON MCGEE, CLERK

Register of Deeds Stamp & File
 Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, JAMES H. MOORE, in a field survey on AUGUST 25, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-10 1/4 CORNER COMMON TO SECTIONS 29 - 30
 CEDAR POST BY JOHN BURT D.S. 1849
 CEDAR 10" N 85° W 88 LINKS
 CEDAR 8" S 72° E 7 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10 FOUND 1" PIPE WITH 4" MICHIGAN DEPARTMENT
 OF CONSERVATION BRASS CAP, SET BY BILL BUCKLER
 R.L.S. #08887.

1960 BEARING TREES
 ASPEN 8" WEST 3 1/2 LINKS
 ASPEN 6" S 84° E 30 1/2 LINKS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


C-10 FOUND ABOVE DESCRIBED MONUMENT IN PLACE.
 NEW WITNESSES.

3" BALSAM	N 75° W(M.B.)	31.86'	NAIL/TAG
4" BALSAM	N 15° W(M.B.)	40.45'	NAIL/TAG
WHITE PINE	S 77° E (M.B.)	21.25'	NAIL/TAG
4" BALSAM	S 32° E (M.B.)	34.00'	NAIL/TAG
CARSONITE MARKER	SOUTH	0.80'	

ACCEPTED BY THE DICKINSON COUNTY
 SURVEY PEER GROUP AS THE OFFICIAL
 CORNER UNDER MICHIGAN PUBLIC ACT
 345 OF 1990 AT A MEETING HELD ON
1-23-99

 COUNTY REPRESENTATIVE

Signed by James H. Moore Date 11-8-99
 Surveyor's Michigan License No. P.S. 28423



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1978
 REVISED JAN., 1983
 REVISED OCT., 1995

ACCEPTED BY THE DICKINSON COUNTY
 SURVEY PEER GROUP AS THE OFFICIAL
 CORNER UNDER MICHIGAN PUBLIC ACT
 345 OF 1990 AT A MEETING HELD ON