

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12: 25

For corners in

Dickinson
(County)
Norway Twp.

Located in: Corner Code #

1. Public Land Survey

T41NR 29W K-8

T___ R___ C-11

T___ R___

T___ R___

2. Property Controlling in Section

S___ T___ R___

S___ T___ R___

3. Miscellaneous Property in Sec.

S___ T___ R___

S___ T___ R___

REMOVED SECTION

WILL 1999

SECTION

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Robert F. Perkins, in a field survey on Nov. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23	●	24	
9													
10		30		29		28		27		26		25	
11			●										
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-8 1/4 Corner Common to Sections 23/24
Post by John Burt, D.S. 1849
Original Bearing Trees
Y. Pine 18" N43°E 25 Lk.
Y. Pine 18" S60°W 19 Lk.

C-11 Corner Common to Sections 29-30-31-32
Post by John Burt, D.S. 1849
Original Bearing Trees
Hemlock 12" N44°W 50 Lk.
Hemlock 14" S33°E 50 Lk.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 No Evidence of Original Corner or its Accessories Found.
Found 1" Pipe Monument with 4" D.N.R. Brass Cap set by Billy D. Buckler, RLS in 10-2-1959 (Old Corner Report #405)
1959 Bearing Trees:
W. Pine 18" N11°W 21 Lk.
W. Pine 16" N53°E 23 Lk. (Found)

C-11 No Evidence of Original Corner or its Accessories Found.
Found 1" Iron Pipe with 4" D.N.R. Brass Cap set by Billy D. Buckler, RLS in 1955 (Old Corner Report #100)
1955 Bearing Tree:
White Pine Stump 36" S56°E 13 Lk.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Found and Accepted Pipe Monument described in "B" above.
New Witnesses:
W. Pine 4" N46°W(M.B.) 60.62' Nail/Tag
W. Pine 4" S62°E(M.B.) 44.80' Nail/Tag
W. Pine 10" S47°W(M.B.) 71.10' Nail/Tag
W. Pine 30" N55°E(M.B.) 16.46' Nail/Tag
Placed Carsonite Marker 1.0' West

C-11 Found and Accepted Pipe Monument described in "B" above.
New Witnesses:
J. Pine 12" S77°W(M.B.) 58.15' Nail/Tag
Fir 5" N58°W(M.B.) 48.90' Nail/Tag
Fir 6" S48°E(M.B.) 41.98' Nail/Tag
Spruce 6" N17°E(M.B.) 7.03' Nail/Tag
Placed Carsonite Marker 1.0' South.

Signed by Robert F. Perkins


Date Nov. 20, 1998

Surveyor's Michigan License No. 12027

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 12027

12-7-98

Robert F. Perkins
COUNTY REPRESENTATIVE



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

Liber 2 Page 407