

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A.**  
**1970**

RECORDED

1999 NOV 30 PM 3:31

For corners in

DICKINSON Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)  
 NORWAY TOWNSHIP

REGISTER OF DEEDS  
 DICKINSON COUNTY  
 RON MOORE, CLERK

1. Public Land Survey T 41 N R 29 W E-11  
 T 41 N R 29 W E-12  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_ SURVEY &  
 in Section S \_\_\_ T \_\_\_ R \_\_\_ RECONUMENTATION  
 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
 Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_  
 MAR 24 2000

Register of Deeds Stamp & File  
 Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, JAMES H. MOORE, in a field survey on AUGUST 25, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-11 CORNER COMMON TO SECTIONS 28-29-32-33 SET POST BY JOHN BURT, D.S. 1849  
 CEDAR 18" S 27° E 76 LINKS  
 WHITE PINE 18" N 36° W 34 LINKS

E-12 ¼ CORNER COMMON TO SECTIONS 32-33 POST SET BY JOHN BURT, D.S. 1849  
 CEDAR 12" S 75° W 129 LINKS  
 CEDAR 20" N 42° E 40 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11 FOUND 1" PIPE WITH 4" MICHIGAN DEPARTMENT OF CONSERVATION ALUMINUM CAP, SET BY BILL BUCKLER R.L.S. #08887.  
 1955 BEARING TREE  
 WHITE SPRUCE 14" S 71° E 151 LINKS

E-12 FOUND 1" PIPE WITH 4" MICHIGAN DEPARTMENT OF CONSERVATION ALUMINUM CAP, SET BY BILL BUCKLER R.L.S. #08887.  
 1961 BEARING TREES  
 SOFT MAPLE 9" S 82° E 57 LINKS  
 CEDAR 8" N 48° W 69 LINKS


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 FOUND ABOVE DESCRIBED MONUMENT IN PLACE NEW WITNESSES.  
 4" WHITE BIRCH S 57° E (M.B.) 45.45' NAIL/TAG  
 6" CEDAR N 52° W (M.B.) 46.47' NAIL/TAG  
 7" BALSAM N 36° W (M.B.) 47.32' NAIL/TAG  
 6" SPRUCE N 2° E (M.B.) 52.60' NAIL/TAG  
 CARSONITE MARKER SOUTH 1.00'

E-12 FOUND ABOVE DESCRIBED MONUMENT IN PLACE NEW WITNESSES.  
 FOUND 16" CEDAR N 47° W (M.B.) 45.32' NAIL/TAG  
 10" SOFT MAPLE N 15° E (M.B.) 32.25' NAIL/TAG  
 5" SOFT MAPLE S 62° E (M.B.) 9.03' NAIL/TAG  
 6" SOFT MAPLE S 30° E (M.B.) 21.05' NAIL/TAG  
 9" BASSWOOD S 50° W (M.B.) 22.12' NAIL/TAG  
 CARSONITE MARKER SOUTH 0.80'

Signed by James H. Moore  
 Surveyor's Michigan License No. 28423

Date 11-8-99



ACCEPTED BY THE DICKINSON COUNTY CLERK  
 CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON  
 11-23-99  
 REVISOR: JAMES H. MOORE  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1995

Liber 3

PAGE 5