

RECORDED

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 1998 DEC 14 PM 12:24

For corners in

Dickinson (County) Norway Twp.

Located In:

Corner Code #

1. Public Land Survey

T 41NR 29W

F-7

T R

K-4

T R

T R

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

REGISTER OF DEEDS DICKINSON COUNTY

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat SECTION 5. Private Claims

I, Robert F. Perkins, in a field survey on Nov. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numerical data and two black dots at grid intersections.

A. Description of original monument and accessories and/or subsequent restoration:

F-7 1/4 Corner Common to Sections 16 Post by John Burt, D.S. 10-2-1849 Original Bearing Trees W. Pine 24" N40°W 3 Lk. Cedar 8" S80°E 12 Lk.

K-4 1/4 Corner Common to Sections 11/12 Cedar Post by John Burt, D.S. 10-4-1849 Original Bearing Trees Y. Birch 8" N23°W 25 Lk. W. Pine 30" S35°E 14 Lk.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7 No Evidence of Original Corner or its Accessories Remain Found 1" D.N.R. Pipe Monument set by Billy D. Buckler, RLS 1-27-1956 from 2 G.L.O. Bearing Trees. Corner Report #105 1956 Bearing Trees: W. Pine 12" N45°E 79 Lk. (Found) Tamarack 10" S68°E 55 Lk. (Found)

K-4 No Evidence of Original Corner or Accessories Found. Found 1" D.N.R. Pipe Marker with 4" Brass Cap set by Billy D. Bucker, RLS 9-23-1959. 1959 Bearing Trees: Aspen 8" S42°W 14 Lk. Spruce 4" N75°E 22 Lk. Spruce 6" N46°W 12 Lk.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7 Found and Accepted Pipe Marker described in "B" above. New Witnesses: Db1. Spruce 8" N48°W(M.B.) 12.60' Nail/Tag W. Pine 18" N45°E(M.B.) 52.90' Nail/Tag Tamarack 12" S68°E(M.B.) 36.60' Nail/Tag Cherry 6" S18°W(M.B.) 43.0' Nail/Tag Placed Carsonite Marker 1.0' South.

K-4 Found and Accepted Pipe Marker described in "B" above. New Witnesses: Spruce 8" N55°W(M.B.) 8.30' Nail/Tag Spruce 14" S70°E(M.B.) 14.25' Nail/Tag Spruce 12" S11°E(M.B.) 7.52' Nail/Tag Fir 10" S25°W(M.B.) 3.75' Nail/Tag Placed Carsonite Marker 1.0' North

Signed by Robert F. Perkins

Date Nov. 20, 1998

Surveyor's Michigan License No. 12027 ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN P.A. 74 OF 1970 AT A MEETING HELD ON 12-7-98