

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12:25

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
Norway Twp.		
1. Public Land Survey	T 41N R 29W	K-8
	T R	C-11
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS
 DICKINSON COUNTY
 1998 DEC 14 PM 12:25

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

SECTION

I, Robert F. Perkins, in a field survey on Nov. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-8 ¼ Corner Common to Sections 23/24 Post by John Burt, D.S. 1849 Original Bearing Trees Y. Pine 18" N43°E 25 Lk. Y. Pine 18" S60°W 19 Lk.	C-11 Corner Common to Sections 29-30-31-32 Post by John Burt, D.S. 1849 Original Bearing Trees Hemlock 12" N44°W 50 Lk. Hemlock 14" S33°E 50 Lk.
---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 No Evidence of Original Corner or its Accessories Found. Found 1" Pipe Monument with 4" D.N.R. Brass Cap set by Billy D. Buckler, RLS in 10-2-1959 (Old Corner Report #405) 1959 Bearing Trees: W. Pine 18" N11°W 21 Lk. W. Pine 16" N53°E 23 Lk. (Found)	C-11 No Evidence of Original Corner or its Accessories Found. Found 1" Iron Pipe with 4" D.N.R. Brass Cap set by Billy D. Buckler, RLS in 1955 (Old Corner Report #100) 1955 Bearing Tree: White Pine Stump 36" S56°E 13 Lk.
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Found and Accepted Pipe Monument described in "B" above. New Witnesses: W. Pine 4" N46°W(M.B.) 60.62' Nail/Tag W. Pine 4" S62°E(M.B.) 44.80' Nail/Tag W. Pine 10" S47°W(M.B.) 71.10' Nail/Tag W. Pine 30" N55°E(M.B.) 16.46' Nail/Tag Placed Carsonite Marker 1.0' West	C-11 Found and Accepted Pipe Monument described in "B" above. New Witnesses: J. Pine 12" S77°W(M.B.) 58.15' Nail/Tag Fir 5" N58°W(M.B.) 48.90' Nail/Tag Fir 6" S48°E(M.B.) 41.98' Nail/Tag Spruce 6" N17°E(M.B.) 7.03' Nail/Tag Placed Carsonite Marker 1.0' South.
---	---

Signed by Robert F. Perkins

Date Nov. 20, 1998

Surveyor's Michigan License No. 12027

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

12-7-98
Bob Perkins
 COUNTY REPRESENTATIVE

