

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12: 25

For corners in

<u>Dickinson</u> (County)	Located in:	Corner Code #
Norway Twp.		
1. Public Land Survey	T <u>41</u> R <u>29W</u>	<u>M-4</u>
	T <u> </u> R <u> </u>	<u>M-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

REGISTER OF DEEDS
 DICKINSON COUNTY
 REGISTERED

**SURVEY &
 REMONUMENTATION**

APR 02 1999

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert F. Perkins, in a field survey on Nov. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| M-4 East 1/4 Corner Section 12
Post by Wm. A. Burt, D.S. 1846
Original Bearing Trees
Cedar 6" S44°E 12 Lk.
Cedar 14" N57°W 35 Lk. | M-5 Southeast Corner Section 12
Post by W. A. Burt, D.S. 1846
Original Bearing Trees
Fir 6" S80°W 7 Lk.
Fir 8" N68°E 15 Lk. |
|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|---|---|
| M-4 No Evidence or Original Corner or its Accessories Remain.
Found 1" Iron Pipe Monument with 4" D.N.R. Cap set by Billy D. Buckler, RLS from G.L.O. BT's in 1957. (Old Report #291)
1957 Bearing Trees:
Cedar 24" N71°W 80 Lk. (Found)
Cedar 15" S33°W 11 Lk. (Found) | M-5 No Evidence of Original Corner or Accessories Found.
Found 1 1/2" Iron Pipe Found by Billy D. Buckler, RLS in 1957 and referred to in Old Corner Report #290.
1957 Bearing Trees:
Tamarack 8" S65°E 36 Lk. (Found)
Tamarack 7" S20°W 54 Lk. (Found) |
|---|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| M-4 Found and Accepted Pipe Marker described in "B" above.
Witnesses:
Cedar 30" N68°W(M.B.) 53.10' Ex. B.T.
Cedar 30" S32°W(M.B.) 7.45' Ex. B.T.
Cedar 12" S25°E(M.B.) 25.53' Nail/Tag
Fir 6" N71°E(M.B.) 18.48' Nail/Tag
Placed Carsonite Marker 1.0' South | M-5 Found and Accepted Corner described in "B" above.
Set 3 1/2" Stamped D.C. Remon Corner inside of Existing Iron Pipe.
New Witnesses:
Spruce 8" N77°W(M.B.) 22.23' Nail/Tag
Spruce 6" N63°E(M.B.) 20.52' Nail/Tag
Tamarack 12" S22°W(M.B.) 35.95' Nail/Tag
Tamarack 10" S67°E(M.B.) 24.30' Nail/Tag
Placed Carsonite Marker 1.0' South |
|--|---|

Signed by Robert F. Perkins
 Surveyor's Michigan License No. 12027
 SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-7-98
R.F. Perkins
 COUNTY REPRESENTATIVE

Date Nov. 20, 1998