

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12: 25

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
<u>Norway Twp.</u>		
1. Public Land Survey	T <u>41</u> R <u>29W</u>	<u>M-4</u>
	T _____ R _____	<u>M-5</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
 DICKINSON COUNTY
 RON MOUTRIER, CLERK

SURVEY & REMONUMENTATION

APR 02 1999

SECTION _____
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert F. Perkins, in a field survey on Nov. 9, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-4 East 1/4 Corner Section 12
 Post by Wm. A. Burt, D.S. 1846
 Original Bearing Trees
 Cedar 6" S44°E 12 Lk.
 Cedar 14" N57°W 35 Lk.

M-5 Southeast Corner Section 12
 Post by W. A. Burt, D.S. 1846
 Original Bearing Trees
 Fir 6" S80°W 7 Lk.
 Fir 8" N68°E 15 Lk.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 No Evidence or Original Corner or its Accessories Remain.
 Found 1" Iron Pipe Monument with 4" D.N.R. Cap set by Billy D. Buckler, RLS from G.L.O. BT's in 1957. (Old Report #291)
 1957 Bearing Trees:
 Cedar 24" N71°W 80 Lk. (Found)
 Cedar 15" S33°W 11 Lk. (Found)

M-5 No Evidence of Original Corner or Accessories Found.
 Found 1 1/2" Iron Pipe Found by Billy D. Buckler, RLS in 1957 and referred to in Old Corner Report #290.
 1957 Bearing Trees:
 Tamarack 8" S65°E 36 Lk. (Found)
 Tamarack 7" S20°W 54 Lk. (Found)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 Found and Accepted Pipe Marker described in "B" above.
 Witnesses:
 Cedar 30" N68°W(M.B.) 53.10' Ex. B.T.
 Cedar 30" S32°W(M.B.) 7.45' Ex. B.T.
 Cedar 12" S25°E(M.B.) 25.53' Nail/Tag
 Fir 6" N71°E(M.B.) 18.48' Nail/Tag
 Placed Carsonite Marker 1.0' South.

M-5 Found and Accepted Corner described in "B" above.
 Set 3 1/4" Stamped D.C. Remon Corner inside of Existing Iron Pipe.
 New Witnesses:
 Spruce 8" N77°W(M.B.) 22.23' Nail/Tag
 Spruce 6" N63°E(M.B.) 20.52' Nail/Tag
 Tamarack 12" S22°W(M.B.) 35.95' Nail/Tag
 Tamarack 10" S67°E(M.B.) 24.30' Nail/Tag
 Placed Carsonite Marker 1.0' South

Signed by Robert F. Perkins
 Surveyor's Michigan License No. 12027
 SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-7-98
ROBERT PERKINS
 COUNTY REPRESENTATIVE

Date Nov. 20, 1998

Libor 2 Page 408