

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code-##
1. Public Land Survey	T <u>41N</u> R <u>29W</u>	<u>M-10</u>
	T " R "	<u>M-11</u>
	T R	
	T R	
2. Property Controlling in Section	S <u>25</u> T <u>41N</u> R <u>29W</u>	<u>7</u>
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTERED DEEDS
 DIVISION
 NOVEMBER 11, 1993
 11:09 AM
 RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Edward Kazianka, in a field survey on Oct. 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 M-10 Cedar 16 as Quarter Corner. No bearing trees.
 Dept. of Conservation Brass cap on iron pipe. 9-13-60
 Cedar 10 N55W 73 lks. Cedar 8 S05E 28 lks. (Note: Believe distance should have been 23 lks.)
 M-11 Wood Post Cedar 32 S85E 15 lks. Cedar 20 N82W 12 lks.
 " 36 S46W 43 lks.
 Dept. of Conservation Brass cap on iron pipe. 2-21-55
 Cedar 10 S60E 29 lks. Cedar 12 S85W 30 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 M-10 Dept. of Conservation corner.
 M-11 " " "

7 Section Corner 1/4 mile north and Quarter Corner 1/4 mile south are set. Set N 1/16th corner at the mid-point and on line between the two noted corners.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 6-7-94
EOP
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-10 Dept. of Conservation corner. Cedar 13 S05E 15.34 feet. Cedar 14 N55W 48.06 ft. Maple 8 S83W 43.80 feet. B. Ash 6 N52E 24.55 feet.
 M-11 Dept of Conservation corner. Cedar 16 S57E 19.48 feet. Cedar 14 S89W 20.05 ft. Cedar 12 N40W 14.87 feet. Cedar 13 N71E 41.09 feet.
 # 7 1 1/2" Alum cap on a 3 foot # 5 re-rod. Maple 15 N73W 5.44 feet. Dbl Maple 8 N34E 26.55 feet. Maple 13 N89E 34.05 feet. Maple 11 S36E 37.20 feet.

Signed by Edward Kazianka Date Nov. 3, 1993
 Surveyor's Michigan License No. 19765



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 28, 1971
 REVISED MAR 14, 1976
 REVISED JAN., 1983

Label 2 Page 71