

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Dickinson

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 29 K. W.	17
2. PROPERTY CONTROLLING IN SECTION	22, T. 41 N. R. 29 K. W.	7
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above were, in a field survey on August 4, 1976, established re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 17 (Section Corner 14, 15, 22, & 23, T41N, R29W):

Found a 1" I.D. x 4' iron pipe with 4" brass cap (DNR) as set by B. D. Buckler, R.L.S. #8887 on 4/23/59. Buckler's record states: "Re-established from line tree 29.25 ch. W; twp. line 2 miles E; sec. cor. 1 mile N; and line tree 51.44 ch. S. Swamp edge 2.00 ch. N checks with Govt. Field notes. Corner lies in old logging road. Found 28" W. Pine stub blazed years ago at cor. Cor. placed and wit. 4/23/59 with H. S. Peterson, D.F. and N. Sperhake, Marquette."

Corner 7 (North 1/16 corner between Sections 22 & 23, T41N, R29W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 17: Found one of Buckler's NBT's cut down. Buckler's record gives no distances to his NBT's, which are as follows:

- ** Cedar 8 N45°W (S15, NBT)
- * Cedar 8 S 5°E (S23, NBT) (Has been cut; only stump remains)
- White Pine 10 N79°E (S14, NBT)

Corner 7: Established on line between monuments at Sec. Cor. 20.062 ch. N and at 1/4 cor. 20.062 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 17: Same monument as described in A, above.

- * Cedar stump 12 S1°E (mag.) 17.9 ft.
- ** Cedar 12 N38°W (mag.) 20.3 ft. "S15, NBT"
- Cedar 8 S 1°E (mag.) 21.9 ft. "S23, NBT"

Corner 7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

- Cedar 8 S22°W (mag.) 8.2 ft. "1/16S, BT"
- Cedar 10 N42°W (mag.) 15.2 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE December 21, 1976
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY Arthur O. Enger DATE December 21, 1976
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

